

Helsinki 31.03.2004

ETUOIKEUSTODISTUS
PRIORITY DOCUMENT



Hakija
Applicant

1. Wärtsilä Finland Oy, Vaasa, FI
2. Mahlanen, Timo, Helsinki, FI

Kansainvälinen patenttihakemus nro
International patent application no PCT/FI2004/050009

Kansainvälinen tekemispäivä
International filing date 30.01.2004

Etuoiikeushak. nro
Priority from appl. FI 20031848

Tekemispäivä
Filing date 18.12.2003

Keksinnön nimitys
Title of invention

REC'D 20 APR 2004

WIPO

PCT

"Gas supply arrangement of a marine vessel and method of controlling
gas pressure in a gas supply arrangement of a marine vessel"

Täten todistetaan, että oheiset asiakirjat ovat tarkkoja jäljennöksiä
kansainvälisiä patenttihakemuksia vastaanottavana viranomaisena
toimivalle Patentti- ja rekisterihallitukselle alkuaan annetuista
anomuslomakkeista, selityksestä, patenttivaatimuksista, tiivistelmästä
ja piirustuksista sekä niihin tehdyistä korjauksista.

This is to certify that the annexed documents are true copies of the
request form, description, claims, abstract and drawings, originally
filed with the Finnish Patent Office acting as receiving Office for the
international patent applications, and of any corrections thereto.

PRIORITY DOCUMENT
SUBMITTED OR TRANSMITTED IN
COMPLIANCE WITH
RULE 17.1(a) OR (b)

Marketta Tehikoski

Marketta Tehikoski
Apulaistarkastaja

Maksu 50 €
Fee 50 €

Maksu perustuu kauppa- ja teollisuusministeriön antamaan asetukseen 1027/2001
Patentti- ja rekisterihallituksen maksullisista suoritteista muutoksineen.

The fee is based on the Decree with amendments of the Ministry of Trade and Industry
No. 1027/2001 concerning the chargeable services of the National Board of Patents and
Registration of Finland.

HOME COPY

1/4

PCT REQUEST

1934WO-JR-TK

Duplicate of original printed on Friday, 30 January, 2004 02:32:17 PM

0	For receiving Office use only	
0-1	International Application No.	PCT/FI/2004/050009
0-2	International Filing Date	30 JAN 2004 (30-01-2004)
0-3	Name of receiving Office and "PCT International Application"	The Finnish Patent Office PCT International Application
0-4	Form - PCT/RO/101 PCT Request	
0-4-1	Prepared using	epoline® online filing PCT plug-in (updated 30.01.2004)
0-5	Petition	
	The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty	
0-6	Receiving Office (specified by the applicant)	National Board of Patents and Registration (Finland) (RO/FI)
0-7	Applicant's or agent's file reference	1934WO-JR-TK
I	Title of invention	GAS SUPPLY ARRANGEMENT OF A MARINE VESSEL AND METHOD OF CONTROLLING GAS PRESSURE IN A GAS SUPPLY ARRANGEMENT ⁴⁴ [IX] OF A MARINE VESSEL
II	Applicant	
II-1	This person is:	applicant only
II-2	Applicant for	all designated States except US
II-4	Name	WÄRTSILÄ FINLAND OY
II-5	Address:	Tarhaajantie 2 FIN-65380 Vaasa Finland
II-6	State of nationality	FI
II-7	State of residence	FI
II-8	Telephone No.	+358 10 709 0000
II-9	Facsimile No.	+358 10 709 5700
III-1	Applicant and/or inventor	
III-1-1	This person is:	applicant and inventor
III-1-2	Applicant for	US only
III-1-4	Name (LAST, First)	MAHLANEN, Timo
III-1-5	Address:	Prikitie 2 A FIN-00850 Helsinki Finland
III-1-6	State of nationality	FI
III-1-7	State of residence	FI

DELETED
BY RO/FI

PCT REQUEST

1934WO-JR-TK

Duplicate of original printed on Friday, 30 January, 2004 02:32:17 PM

IV-1	Agent or common representative; or address for correspondence The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:	agent
IV-1-1	Name	AWEK INDUSTRIAL PATENTS LTD OY
IV-1-2	Address:	P.O.Box 230 FIN-00101 Helsinki Finland
IV-1-3	Telephone No.	+358 9 2514 6160
IV-1-4	Facsimile No.	+358 9 2514 6168
IV-1-5	e-mail	awek@awekip.fi
V	Designation of States	
V-1	Regional Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AP: BW GH GM KE LS MW MZ SD SL SZ TZ UG ZM ZW and any other State which is a Contracting State of the Harare Protocol and of the PCT EA: AM AZ BY KG KZ MD RU TJ TM and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT EP: AT BE BG CH&LI CY CZ DE DK EE ES FI FR GB GR HU IE IT LU MC NL PT RO SE SI SK TR and any other State which is a Contracting State of the European Patent Convention and of the PCT OA: BF BJ CF CG CI CM GA GN GQ GW ML MR NE SN TD TG and any other State which is a member State of OAPI and a Contracting State of the PCT
V-2	National Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AE AG AL AM AT AU AZ BA BB BG BR BW BY BZ CA CH&LI CN CO CR CU CZ DE DK DM DZ EC EE EG ES FI GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR KZ LC LK LR LS LT LU LV MA MD MG MK MN MW MX MZ NI NO NZ OM PG PH PL PT RO RU SC SD SE SG SK SL SY TJ TM TN TR TT TZ UA UG US UZ VC VN YU ZA ZM ZW

PCT REQUEST

1934WO-JR-TK

Duplicate of original printed on Friday, 30 January, 2004 02:32:17 PM

V-5	Precautionary Designation Statement In addition to the designations made under items V-1, V-2 and V-3, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) of the State(s) indicated under item V-6 below. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit.	
V-6	Exclusion(s) from precautionary designations	NONE
VI-1	Priority claim of earlier national application	
VI-1-1	Filing date	18 December 2003 (18.12.2003)
VI-1-2	Number	20031848
VI-1-3	Country	FI
VI-2	Priority document request The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) identified above as item(s):	VI-1
VII-1	International Searching Authority Chosen	Swedish Patent Office (ISA/SE)
VIII	Declarations	Number of declarations
VIII-1	Declaration as to the identity of the inventor	-
VIII-2	Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent	-
VIII-3	Declaration as to the applicant's entitlement, as at the international filing date, to claim the priority of the earlier application	-
VIII-4	Declaration of inventorship (only for the purposes of the designation of the United States of America)	-
VIII-5	Declaration as to non-prejudicial disclosures or exceptions to lack of novelty	-

PCT REQUEST

1934WO-JR-TK

Duplicate of original printed on Friday, 30 January, 2004 02:32:17 PM

IX	Check list	number of sheets	electronic file(s) attached
IX-1	Request (including declaration sheets)	4	-
IX-2	Description	9	1934wo.pdf
IX-3	Claims	3	1934wo.pdf
IX-4	Abstract	1	1934wo.pdf
IX-2b	Pre-conversion archive	-	-
IX-5	Drawings	1	1934wo-drawings.pdf
IX-7	TOTAL	18	
	Accompanying Items	paper document(s) attached	electronic file(s) attached
IX-8	Fee calculation sheet	-	Fees . PDF
IX-19	Figure of the drawings which should accompany the abstract	1	
IX-20	Language of filing of the international application	English	
X-1	Signature of applicant, agent or common representative		
X-1-1	Signed by	Subject: FI, RISTOLA JARI 13149006F Issuer: FI, Vaestorekisterikeskus CA, VRK Gov. CA for Citizen Qualified Certificates	
X-1-2	Capacity	WÄRTSILÄ FINLAND OY (Applicant 1)	

AWEK INDUSTRIAL PATENTS LTD OY (Agent 1)

FOR RECEIVING OFFICE USE ONLY

10-1	Date of actual receipt of the purported international application	30 JAN 2004 (30-01-2004)
10-2	Drawings:	
10-2-1	Received	
10-2-2	Not received	
10-3	Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application	
10-4	Date of timely receipt of the required corrections under PCT Article 11(2)	
10-5	International Searching Authority	ISA/SE
10-6	Transmittal of search copy delayed until search fee is paid	

FOR INTERNATIONAL BUREAU USE ONLY

11-1	Date of receipt of the record copy by the International Bureau	
------	--	--

DELETED
BY RO/FI

RO/FI

GAS SUPPLY ARRANGEMENT OF A MARINE VESSEL AND METHOD OF CONTROLLING GAS PRESSURE IN A GAS SUPPLY ARRANGEMENT OF A MARINE VESSEL

- 5 Invention relates to a gas supply arrangement of a marine vessel according to preamble of claim 1 and to method of controlling gas pressure in a gas supply arrangement of a marine vessel according to the preamble of claim 11.

10 The propulsion system of LNG (Liquified Natural Gas) tankers is usually powered by making use of the cargo. Storing of the gas in the tanker is arranged by using heat insulated cargo tanks into which an ullage space section and a liquid phase section are formed. The pressure in the cargo tanks is approximately at atmospheric pressure level and the temperature of the liquefied gas is about minus 163 °C. Although the insulation of the cargo tank is extremely good, gradually increasing of the LNG temperature causes formation of so called natural boil-off gas. The natural boil-off gas must be removed in order to avoid extensive increasing of pressure in the cargo tanks. The natural boil-off gas may be utilised in tanker's consumption devices like propulsion system. However, the amount of natural boil-off gas is not sufficient for providing all propulsion energy required in all circumstances and therefore the vessel must be provided with additional means for acquiring extra gas, so called forced boil-off gas. Additionally the usage of the gas as source of propulsion energy sets requirements for the pressure level and stability of the gas.

- 25 For example in a patent publication FR 2722760 there is shown an arrangement in which liquid gas is supplied to a so called forced boiling vaporiser in which the liquid gas vaporises into gas form, which in turn may be combined with the natural boil-off gas.

- 30 EP 1348620 A1 shows a gas supply apparatus in which the natural boil-off gas is led to a compressor, which increase the pressure of the gas prior to feeding it to

- consumption via a feed line. The capacity of the compressor feeding the natural boil-off gas is controlled by the pressure at the feed line. Additionally, the apparatus also includes a forced boiling vaporiser in which the liquid gas previously pumped to the higher pressure is vaporised. In this arrangement the forced boiling
- 5 gas portion is combined to the natural boil-off gas after the pressure of the natural boil-off gas has been increased. This arrangement is mentioned to decrease the work required to compress the gas to a given pressure. It has, however, some problems, which are discussed below.
- 10 The supply amount of the forced boiling gas is controlled by on-off valve positioned prior to the vaporiser, the control being based on the gas cargo tank pressure. The operation of the pump is also controlled by on-off control based on the pressure of the gas cargo tank. The line between the gas cargo tank and the vaporiser has also a branch for returning a part of pumped liquid gas back to the gas cargo tank.
- 15 The amount of returned part is controlled based on the pressure of the gas line before the vaporiser. A problem in this arrangement is the returning of the pumped liquid gas back to the cargo tank. That is not desired due to the heating effect of the liquid gas slightly warmed up by the pumping and circulation.
- 20 As the consumption of the gas at the outlet side (the feed line) of the vaporiser and compressor varies, the process must be controlled so that the pressure in the gas cargo tank and/or in the feed line will not rise too much and so that required amount of gas may be supplied. When the formation of the natural boil-off gas is not strong enough or consumption is suddenly increasing, the pressure in the ul-
- 25 lage space of the gas cargo tank decreases and the operation of forced boiling vaporiser and liquid gas pump is started. After operating the pump and the vaporiser a while the pressure will increase to adequate level. Then the pump may be shut down and the valve of the forced boiling vaporiser is also closed. Particularly because the operation of the vaporiser is on-off controlled, the variation of the pres-
- 30 sure in the feed line is inevitably very strong. This is even more emphasised by the fact that the vaporiser is typically dimensioned for 100% consumption, which

makes the control very rough. Therefore, this kind of a control system is very complicated and also somewhat unstable. Similar arrangement to this is shown in EP 1291576 A2.

- 5 An objective of the invention is to provide a gas supply arrangement for a marine vessel, which solves the above mentioned and other problems of the prior art. It is also an objective of the invention to provide a method of controlling gas pressure in a gas supply arrangement for a marine vessel with liquefied gas cargo tank, which provides even pressure at the feed line and reliable gas supply for consumption
10 devices of the vessel.

- Objectives of the invention are met substantially as is disclosed in claims 1 and 11, and in more detailed manner in other claims. In the following the invention will be described with a reference mainly to one cargo tank. However, it is clear that a ma-
15 rine vessel may be provided with several cargo tanks each having an individual gas supply arrangement or several cargo tanks may be connected parallel having a shared gas supply arrangement.

- According to the invention, the gas supply arrangement of a marine vessel being
20 adapted to carry liquefied gas in its cargo tank having an ullage space section and a liquid phase section and to utilise the cargo as fuel to provide power for the vessel, comprises

- a first gas supply line, which connects an ullage space section of the cargo tank and a gas main supply line and which is provided with a compressor for raising the
25 pressure of the gas to an adequate level, and
- a second gas supply line, which connects liquid phase section of the cargo tank and the gas main supply line and which is provided with at least a pump for raising the pressure of the liquid gas and for pumping it forward.

- It is mainly characteristic to the invention that the second gas supply line is addi-
30 tionally provided with a gas reservoir having an ullage space section and liquid phase section, which reservoir is connected to the liquid phase section of the cargo

tank by a first duct section of the second gas supply line and to the gas main supply line by a second duct section of the second gas supply line.

5 Preferably the reservoir is provided with temperature control unit by means of which the pressure in the reservoir may be indirectly controlled. This kind of an arrangement provides a gas supply system, with which the pressure of the gas in the main supply line may be easily controlled and maintained very stable.

10 The temperature control unit of the reservoir comprises adjustable heating device for heating the liquid phase gas in the reservoir. By heating the liquid it is possible to activate gas evaporation of the liquid gas the liquid phase section. The heating device is provided with control device being responsive to the gas pressure in the reservoir. This provides accurate and reliable means for controlling pressure. The reservoir is preferably also provided with surface level control arrangement for
15 controlling the surface level of the liquid phase section. Preferably the heating device is provided with a heat exchanger external to the reservoir being in connection with the liquid phase section of the reservoir by piping. The second duct section of the second gas supply line is preferably provided with an automatically controlled closing valve, which may close the supply of gas quickly in case the gas consump-
20 tion stops rapidly.

The reservoir is advantageously dimensioned to have a volume corresponding to few hours gas consumption through the gas main supply line, which provides a possibility of using the reservoir as buffer gas source. The dimensioning depends
25 on the specific application in question e.g. discharge time of the tanks may be taken into account.

The reservoir is so connected that the first duct section of the second gas supply line extends into a liquid phase section of the reservoir, and the second duct section of the second gas supply line extends from the ullage space section of the
30 reservoir to the gas main supply line.

In the method according to the invention of controlling gas pressure in a gas supply arrangement of a marine vessel with liquefied gas cargo tank having an ullage space section and liquid phase section, and with a gas consumption device, gas
5 from the cargo tank is led to the consumption device via a first gas supply line, which is provided with a compressor, the compressor raising the pressure of natural boil-off gas to an adequate level, and additionally or alternatively via a second gas supply line, which connects liquid phase section of the cargo tank and the gas consumption device, the second gas supply line is provided with a pump for raising
10 the pressure of the liquid gas and pumping it forward. In the second gas supply line gas is fed into a reservoir having an ullage space section and liquid phase section, in which the gas is temporarily stored. From the reservoir gas is further introduced to the gas consumption device. Gas is evaporated in the reservoir and the pressure of the gas in the in the second gas supply line is controlled by controlling the
15 temperature of the liquid phase section of the reservoir.

The invention has several advantages. First of all, the pressure control is very accurate due to the novel way of controlling the pressure by heating the liquid gas. Additionally the invention provides a buffer for gas fuel for the consumption devices
20 in case the connection to the cargo tank must be cut off.

In the following the invention will be described with the reference to the accompanying schematic drawing, in which figure 1 shows a preferred embodiment of the gas supply arrangement according to the invention.
25

Figure 1 shows schematically cross section of a marine vessel 6, like LNG tanker. The vessel 6 is adapted to carry liquefied gas in it cargo tanks. Normally there are several tanks in a tanker, but in the figure 1 only one cargo tank 4 is shown for clarity reasons. The cargo tank 4 is filled so that there is always an ullage space
30 section 4.1 filled with gas in gaseous form and a liquid phase section 4.2 filled with liquefied gas. During the storing of the liquefied gas in the cargo tank 4 the gas is

evaporating changing its phase and transferring to the ullage space 4.1. The evaporated gas, so called natural boil-off gas, may be utilised in a consumption device 5 of the vessel 6. The consumption device 5 is preferably a gas engine providing propulsion power. In the figure only one consumption device 5 is shown but it is clear that there may be several devices.

The vessel 6 is provided with a gas supply arrangement 1, which comprises a first gas supply line 2. The first gas supply line 2 extends from an ullage space section 4.1 of the cargo tank 4 to a gas main supply line 7 leading to the consumption device 5. The first gas supply line 2 is adapted for delivering the evaporated boil-off gas from the cargo tank 4 to the consumption device 5 of the vessel 6 via a main supply line 7. The pressure in cargo tank 4 is maintained slightly over-pressurised. The first gas supply line 2 is provided with a compressor 2.1 for raising the pressure of the boil-off gas to an adequate level for usage in the consumption device 5. The pressure level in the gas main supply line 7 must be maintained at appropriate pressure but below maximum design limits. The lower limit is typically ruled by requirements of the gas engines of the vessel being as the consumption device 5. The capacity of the compressor 2.1 is controlled by making use of pressure measurement device 10 provided in the cargo tank ullage space, so that the pressure in the cargo tank remains within certain design limits.

The gas supply arrangement 1 comprises also a second gas supply line 3. The second supply line 3 is arranged for converting the liquefied gas into gaseous form for example in case the amount of the natural boil-off gas is not big enough. The second supply line 3 is principally parallel line to the first supply line 2, leading from the cargo tank 4 to the main supply line 7. Therefore it is provided with a liquid gas pump 3.1 for raising the pressure of the liquid gas to approximately level of the main supply line 7. The pump 3.1 is preferably positioned in the liquid phase section 4.2 of the cargo tank 4 so that it pumps the gas in liquid form. The converting the liquefied gas into gaseous form is accomplished by providing the second supply line 3 with a gas reservoir 3.2, into which the pump 3.1 transfers the liquid gas

via a first duct section 3.4 of the second gas supply line 3. The first duct section 3.4 is preferably provided with a check valve or automatic controlled close valve 3.12 for preventing the return of the liquid gas back to the cargo tank 4. The pump 3.1 and valve 3.12 are operated under control of a surface level control arrangement 8

5 provided in the reservoir 3.2. The pump is started when the level of the surface is at its lower limit 8.1 and the pump is running until the surface is raised to its upper limit 8.2. Preferably the surface limits are selected so that the reservoir is 20% filled at minimum and 80% filled at maximum. The output of the pump 3.1 is preferably selected so that the ascending speed of the surface is relatively low during the fill-

10 ing. This way the filling of the reservoir 3.2 has minimum impact on the gas pressure in the ullage space section 3.3 of the reservoir 3.2. The effect of the ascending surface to the pressure may be at least partly compensated by properly controlling a reservoir temperature control unit, which will be described later. Due to the properties of the gas i.e. the volume of the gas in gaseous form being approxi-

15 mately 600 times as much as is in liquid form, the output of the pump 3.1 may be selected in this manner without a risking the gas formation capacity. Typically the cargo tank 4 is provided with a so called spray pump, and the pump 3.1 may be a separate pump or the spray pump.

20 Formation of gaseous gas in the reservoir 3.2 is accomplished partly by arranging the ullage space section 3.3 in the reservoir i.e. taking care that the upper limit 8.2 of the surface of the liquid gas is not too high. However, mainly the gas evaporation and simultaneously the pressure level in the ullage space section 3.3 is controlled by controlling the temperature of the liquid phase section 3.7 in the reservoir

25 3.2. This is accomplished by the temperature control unit 3.6. The unit comprises pressure sensor 9 provided in the reservoir, based on measurement value of which the temperature of the liquid phase section 3.7 is controlled. The principle of the control is based on the fact that the higher the temperature, the stronger the evaporation of the gas is. So, when the liquid phase section 3.7 is heated the formation of gaseous gas is increased and the simultaneously the pressure depend-

30 ing on the consumption, of course. This applies also vice versa.

The heating of the liquid gas in the liquid phase section 3.7 is accomplished by a heating device. The heating device according to a preferred embodiment of the invention comprises an external heat exchanger 3.9 into and from which the liquefied gas is flowing through piping 3.10. The liquefied gas is heated by a heat transfer medium flowing in the other side 3.8 of the heat exchanger 3.9. There may be a circulation pump 3.11 for facilitating the flowing of the liquefied gas, but the piping may be so dimensioned that free circulation (based on density difference) will occur. Heat transfer rate and thus heating of the liquefied gas is controlled by a valve 9.1, which controls the flow of the heat transfer medium. The heat transfer medium may be e.g. water or steam, but practically any suitable heat source, also electric heater, may be utilised. In the figure 1 also a possible direct heater 3.9' is shown with dotted line.

Gas from the reservoir is led to the gas main supply line 7 via a second duct section 3.5 of the second gas supply line 3. When the output of the boil-off gas (first gas supply line 2) is not enough for consumption demand, the pressure in the main supply line 7 will modestly decrease and the gas will flow through the second duct section 3.5 from the ullage space 3.3 of the reservoir 3.2. This causes a minor pressure drop in the ullage space 3.3, which is detected by the sensor 9. The measurement is transmitted to a control device (not shown for clarity reasons) which sends a command to the valve 9.1 in order to actuate opening movement. This, in turn, increases the heat transfer from the heat transfer medium to the liquefied gas raising its temperature. And, since temperature of the liquefied gas is raised, the evaporation of the gas is increased and the pressure drop in the ullage space section 3.3 will be compensated. In case other type of heating device would be used its output power would be controlled by the pressure measurement sensor 9.

This kind of a pressure control arrangement is very stable and easy to adjust to maintain the supply line pressure within the required limits. Additionally the reser-

voir 3.2 provides a buffer for example for situation when the cargo tanks 4 must be cut off from the vessel's gas supply. For example while discharging the cargo tank 4 at port terminal, it may be advantageous to have some buffer volume and therefore the reservoir 3.2 may be dimensioned to have a volume corresponding to at least four hours gas consumption through the gas main supply line 7.

The second duct section 3.5 of the second gas supply line 3 is provided with an automatically controlled closing valve 3.13. In case the gas consumption stops rapidly, the valve 3.13 is closed. In this case the pressure in the reservoir 3.2 will be allowed to increase to slightly higher level than normally. The reservoir 3.2 is provided with a pipe 3.14 which opens into the liquid phase section of the reservoir and which leads back to the cargo tank 4. The pipe is provided with a valve 3.15 for controlling the flow of liquid gas. This provides eg. A possibility of returning heavier hydrocarbon compounds back to the cargo tank 4.

15

During the filling of the reservoir 3.2 the pressure in the ullage space 3.3 partly increases due to the ascending surface level, this is registered by the pressure sensor 9, which information is transmitted also to the temperature control unit 3.6.

Control dependencies in the figure 1 is shown informally by dotted lines for clarity reasons. However, it is clear that the control system may be realised by various manners, using centralised or distributed control arrangements.

The invention is not limited to the embodiment shown but several modifications of the invention are conceivable within the scope of the appending claims.

CLAIMS

1. Gas supply arrangement (1) of a marine vessel (6) being adapted to carry liquefied gas in its cargo tank (4) having an ullage space section (4.1) and a liquid phase section (4.2), and to utilise the cargo as fuel to provide power for the vessel, the arrangement comprising
- 5 - a first gas supply line (2), which connects an ullage space section (4.1) of the cargo tank (4) and a gas main supply line (7) and which is provided with a compressor (2.1) for raising the pressure of the gas to an adequate level,
- 10 - a second gas supply line (3) which connects liquid phase section (4.2) of the cargo tank (4) and the gas main supply line (7) and which is provided with at least a pump (3.1) for raising the pressure of the liquid gas and for pumping it forward, **characterised** in that the second gas supply line (3) is provided with a gas reservoir (3.2) having an ullage space section (3.3) and liquid phase section (3.7), which
- 15 reservoir (3.2) is connected to the liquid phase section (4.2) of the cargo tank by a first duct section (3.4) of the second gas supply line (3) and to the gas main supply line (7) by a second duct section (3.4) of the second gas supply line (3).
2. Gas supply arrangement (1) according to claim 1, **characterised** in that, the reservoir (3.2) is provided with temperature control unit (3.6).
- 20 3. Gas supply arrangement (1) according to claim 2, **characterised** in that the temperature control unit (3.6) of the reservoir (3.2) comprises adjustable heating device (3.9, 3.9') for heating the liquid phase gas in the reservoir (3.2).
4. Gas supply arrangement (1) according to claim 1, **characterised** in that the reservoir (3.2) is provided with surface level control arrangement (8) for controlling
- 25 the surface level of the liquid phase section (3.7).
5. Gas supply arrangement (1) according to claim 2, **characterised** in that the heating device (3.9, 3.9') is provided with control device (9, 9.1) responsive to the gas pressure in the reservoir (3.2).

6. Gas supply arrangement (1) according to claim 5, **characterised** in that the heating device (3.9, 3.9') is provided with a heat exchanger external to the reservoir (3.2) being in connection with the liquid phase section (3.7) of the reservoir by piping (3.10).

5 7. Gas supply arrangement (1) according to anyone of the preceding claims 1 - 5, **characterised** in that the reservoir (3.2) is dimensioned to have a volume corresponding to few hours gas consumption through the gas main supply line (7).

10 8. Gas supply arrangement (1) according to claim 1, **characterised** in that the first duct section (3.4) of the second gas supply line (3) extends into a liquid phase section (3.7) of the reservoir (3.2), and that the second duct section (3.5) of the second gas supply line (3) extends from the ullage space section (3.3) of the reservoir (3.2) to the gas main supply line (7).

15 9. Gas supply arrangement (1) according to claim 1, **characterised** in that the second duct section (3.5) of the second gas supply line (3) is provided with an automatically controlled closing valve (3.13).

10. Gas supply arrangement (1) according to claim 1, **characterised** in that the liquid phase section (3.7) of the reservoir (3.2) and the cargo tank (4) are connected with each other with a return line (3.14) provided with a valve (3.15).

20 11. Method of controlling gas pressure in a gas supply arrangement of a marine vessel (6) with liquefied gas cargo tank (4) having an ullage space section (4.1) and liquid phase section (4.2), and a gas consumption device (5), in which gas from the cargo tank (4) is led to the consumption device (5) via a first gas supply line (2) which is provided with a compressor (2.1), the compressor raising the pressure of the boil-off gas to an adequate level, and additionally or alternatively via a
25 second gas supply line (3), which connects liquid phase section (4.2) of the cargo tank (4) and the gas the gas consumption device (5), the second gas supply line (3) being provided with a pump (3.1) for raising the pressure of the liquid gas and pumping it forward, **characterised** in that in the second gas supply line gas is fed

into a reservoir (3.2) having an ullage space section (4.1) and liquid phase section (4.2), in which reservoir (3.2) the gas is temporarily stored and from which gas is introduced to the gas consumption device (5).

- 5 12. Method of controlling gas pressure according to claim 11, **characterised** in that the pressure of the gas in the in the second gas supply line (3) is controlled by controlling the temperature (9,9.1,3.6) of the liquid phase section (3.7) of the reservoir (3.2).

(57) ABSTRACT

Gas supply arrangement (1) of a marine vessel (6) being adapted to carry liquefied gas in its cargo tank (4) having an ullage space section (4.1) and a liquid phase section (4.2), and to utilise the cargo as fuel to provide power for the vessel, the arrangement comprising a first gas supply line (2) which connects an ullage space section (4.1) of the cargo tank (4) and a gas main supply line (7) and which is provided with a compressor (2.1) for raising the pressure of the gas to an adequate level, a second gas supply line (3) which connects liquid phase section (4.2) of the cargo tank (4) and the gas main supply line (7) and which is provided with at least a pump (3.1) for raising the pressure of the liquid gas and for pumping it forward. The second gas supply line (3) is provided with a gas reservoir (3.2) having an ullage space section (3.3) and liquid phase section (3.7), which reservoir (3.2) is connected to the liquid phase section (4.2) of the cargo tank by a first duct section (3.4) of the second gas supply line (3) and to the gas main supply line (7) by a second duct section (3.4) of the second gas supply line (3). Invention relates also to corresponding method.




Fig. 1